

OFF-SITE INSPECTION REQUIREMENTS

Meter Box – Level and Straight

Meter Setter – 18 inches to 20 inches deep and level

Sidewalk – Free of debris and clean for inspection for cracks

Ribbon Curb & Gutter – Clean of debris and clean for inspections of cracks

Swale – Must be to required specifications for sub-division and free from any and all debris

House Address – House number must be on house

IF THESE REQUIREMENTS ARE NOT MET, JUMPERS WILL BE PULLED AND SETTER LOCKED OUT UNTIL REQUIREMENTS CORRECTED AND INSPECTED BY GRANTSVILLE CITY.